

17-22-22W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **SUNRAY MID-CONTINENT OIL COMPANY**
Farm- **Gus Miller "A" No. 2**

SEC. 7 T. 22 R. 22W
 C SE NE

Total Depth. **4640'**
Comm. **4-4-1962** Comp. **4-16-1962**
Shot or Treated.
Contractor. **Garvey Drilling Company**
Issued. **8-18-1962**

County **Hodgeman**
 KANSAS



CASING:
8 5/8" @ 251' W/200 Sks. Cem.,
5 1/2" @ 4636' W/100 Sks. Cem.,

Elevation. **2320' DF.**

Production. **80 BOPD. & 3 BW/Miss.**
4547-77

Figures Indicate Bottom of Formations.

Surface Clay	80
Blue Shale	251
Shale W/Sand Strks.	790
Shale	860
Blaine Anhydrite	870
Shale & Sand	1470
Anhydrite	1510
Shale	1530
Shale & Shells	1760
Shale	2030
Shale & Lime	2460
Lime	2718
Lime & Shale	2935
Shale & Lime	3025
Shale	3190
Shale & Lime	3390
Shale	3535
Shale & Lime	3920
Lime	4230
Lime & Shale	4297
Lime	4370
Lime & Shale	4490
Lime	4640
TOTAL DEPTH	4640

TOPS:	ELECTRIC LOG
Stone Corral	1497
Heebner	3878
Toronto	3896
Douglas	3909
Lansing	3936
Base Kansas City	4237
Cherokee	4452
Mississippi	4546
Total Depth	4640