

8-22-22W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **SUNRAY MID-CONTINENT OILCO.**
Farm- **Gus Miller** No. **4**

SEC. **8** T. **22** R. **22W**
C **NW NW**

Total Depth. **4575'**
Comm. **2-11-62** Comp. **2-22-62**
Shot or Treated.
Contractor. **Garvey Drilg. Co.**
Issued. **6-23-62**

County **Hodgeman**
KANSAS



CASING:
8 5/8" 246' cem w/200 sx.
5 1/2" 4563' cem w/100 sx.

Elevation. **2269' DF**

Production. **65 BOPD & 48 BWPD**

Figures Indicate Bottom of Formations.

top soil & clay	40
shale	90
blue shale	570
shale & red bed	810
Anhydrite	825
shale	900
sand	1100
shale	1439
red bed	1500
shale	1880
shale w/lime strks.	2240
lime	2725
lime & shale	3855
lime	3925
chirty lime	4015
lime	4495
chirty lime	4575
Total Depth	

TOPS: SCOUT	
Blaine	811
Stone Corral	1430
Heebner	3813
Lansing	3871
Base Kansas City	4170
Marmaton	4240
Cherokee Shale	4387
Mississippi Chert	4484
Kinderhook	4569