

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


8-22-22W

Company- SUNRAY MID-CONTINENT OIL CO.  
Farm- Miller Estate No. 3

SEC. 8 T. 22 R. 22W  
C NW NE

Total Depth. 4508'  
Comm. 1-2-62 Comp. 1-14-62  
Shot or Treated.  
Contractor. Garvey Drlg. Co.  
Issued. 5-19-62

County Hodgeman  
KANSAS



CASING:  
8 5/8" 255' cem w/200 sx.  
5 1/2" 4492' cem w/100 sx.

Elevation. 2293' RB

Production. 240 BOPD

Figures Indicate Bottom of Formations.

shale & sand	70
blue shale w/sand strks.	255
blue shale	580
red bed	910
sand & red bed	1210
shale & red bed	1451
Anhydrite	1495
shale & shells	1715
shale	2085
shale w/lime strks.	2340
lime	2735
lime & shale	2952
shale & lime w/chalk strks.	3115
shale & lime	3300
lime & shale	3910
lime	4050
cherty lime	4077
lime	4399
lime & shale	4508
Total Depth	

TOPS: SCOUT	
Heebner	3832
Toronto	3850
Douglas	3864
Base Kansas City	4184
Marmaton	4254
Ft. Scott	4344
Cherokee Shale	4402
Mississippi Osage	4490