

8. 22. 22W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. SUNRAY MID-CONTINENT OIL CO.
Farm. Miller Est. No. 4

SEC. 8 T. 22 R. 22W
C NE NE

Total Depth. 4575'
Comm. 2-22-62 Comp. 3-6-62
Shot or Treated.
Contractor. Garvey Drlg. Co.
Issued. 7-7-62

County Hodgeman
KANSAS



CASING:

8 5/8" 260' cem w/200 sx.
5 1/2" 4574' cem w/100 sx.

Elevation. 2258' DF

Production. 144 BOPD, NW

Figures Indicate Bottom of Formations.

surface clay	40
shale	260
blue shale	560
red bed	750
shale	800
Anhydrite	815
red bed & shale	900
sand	1100
shale	1400
red bed & shale	1428
Anhydrite	1463
shale & shells	1680
shale & lime	2375
lime	2875
shale & lime	3535
lime & shale	3905
lime	4430
lime & shale	4460
cherty lime	4575
Total Depth	

TOPS: SCOUT

Blaine	799
Stone Corral	1430
Heebner	3813
Douglas	3848
Lansing	3871
Base Kansas City	4168
Marmaton	4242
Ft. Scott	4328
Cherokee Shale	4387
Mississippi	4480