

16-22-22W ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ROCK ISLAND OIL & REFINING CO., INC.
Farm- Miller "B" No. 1

SEC. 16 T. 22 R. 22W
C SW NE

Total Depth. 4479'
Comm. 4-23-63 Comp. 5-3-63
Shot or Treated.
Contractor. Murfin Drilling Co.
Issued. 9-14-63

County Hodgeman
KANSAS



CASING:
8 5/8" 276' cem w/200 sx.
5 1/2" 4477' cem w/75 sx.

Elevation. 2223' KB

Production. 50 BOPD, 120 BWPD

Figures Indicate Bottom of Formations.

surface hole	278
shale & sand	850
sand	1031
shale & redbed	1150
shale	1392
Anhydrite	1428
shale	1500
shale-shells	2150
lime & shale	2320
shale-lime	2460
lime-shale	3850
lime	4479 RTD
Total Depth	

TOPS: SAMPLE	
Anhydrite	1392
Heebner	3807
Lime	3864
Base Kansas City	4168
Marmaton	4238
Ft. Scott	4324
Conglomerate	4453
Mississippi	4476

DST #1 4451-79' Op 1 hr, Rec. 720'
very heavily oil & gas cut mud w/free
oil plus 180' oil cut mud & wtr. IF
109#, FF 405#, IBHP 1389#/30 min.
FBHP 1353#/30 min.