

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


17-22-22W

Company- SUNRAY DX OIL COMPANY
 Farm- Ewy No. 2

SEC. 17 T. 22 R. 22W
 C NE SW

Total Depth. 4556'
 Comm. 7-29-62 Comp. 8-12-62
 Shot or Treated.
 Contractor. Garvey Drilling Co.
 Issued. 3-9-63

County Hodgeman
 KANSAS



Elevation. 2240' DF

Production. 235 BOPD, NW

CASING:

8 5/8" 254' cem w/200 sx.
 5 1/2" 4551' cem w/100 sx.

Figures Indicate Bottom of Formations.

surface clay & shale	254
shale	685
red bed	784
Blaine anhydrite	804
red bed & shale	1400
anhydrite	1434
shale & shells	1485
shale	1750
shale & shells	2085
shale & lime	2315
lime	2755
shale & lime	2926
shale	2970
shale & lime	3380
shale & chalky lime	3477
shale	3560
shale & lime	3638
lime	3700
shale & lime	3830
lime	4032
lime & shale	4290
lime	4350
shale & lime	4399
lime & shale	4455
lime	4545
Kinderhook	4556
Total Depth	

TOPS: LOG

Heebner	3792
Toronto	3810
Douglas	3826
Lansing	3851
Base Kansas City	4147
Marmaton	4220
Fort Scott	4310
Cherokee	4369
Mississippi	4456
Kinderhook	4539