

17-22-22W ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- RAINS & WILLIAMSON OIL CO.
Farm- Ewy "B" No. 2

SEC. 17 T. 22 R. 22W
C SE NE

Total Depth. 4518'
Comm. 7-30-63 Comp. 8-10-63
Shot or Treated.
Contractor.
Issued. 1-18-64

County Hodgeman
KANSAS



Elevation. 2283' KB

Production. 86 BOPD, NW

CASING:

8 5/8" 283' cem w/150 sx.
5 1/2" 4511' cem w/125 sx.

Figures Indicate Bottom of Formations.

surface & post rock	40
shale	195
sand & shale	220
shale	540
shale & redbed	800
Anhydrite	830
shale	905
sand	1105
shale	1430
Anhydrite	1475
shale & shells	2225
lime & shale	3240
shale & lime	3855
lime & shale	4010
lime	4405
lime & shale	4503
lime	4518 RTD
Total Depth	

TOPS: LOG

Anhydrite (sample)	800-30
Base Anhydrite (sample)	1430-75
Heebner	3837
Toronto	3854
Lansing	3895
Base Kansas City	4195
Marmaton	4258
Marmaton Zone	4283
Ft. Scott	4356
Cherokee	4415
Mississippi	4510