

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


19-22-22W

Company- PICKRELL DRILLING
Farm- Miller No. 2

SEC. 19 T. 22 R. 22W
C NE NW

Total Depth. 4645'
Comm. 4-20-63 Comp. 5-4-63
Shot or Treated.
Contractor. Pickrell Drlg.
Issued. 11-2-63

County Hodgeman
KANSAS



CASING:

Elevation. 2318 RB

8 5/8" 262' cem w/ 175 sx
5 1/2" 4643.80' cem w/ 140 sx

Production. 150 BOPD - N Wtr.

Figures Indicate Bottom of Formations.

top soil & lime	50	
shale & shells	210	
shale	262	
shale & sand	715	
red bed	845	
Blaine	860	
red bed	940	
sand	1130	
red beds	1240	
red beds, shale & shells	1450	
anhydrite	1510	
shale & shells	1935	
shale & lime shells	2265	
lime & shale	2350	
lime	2810	
lime & shale	3705	
lime & sandy shale	3840	
lime & shale	3940	
lime	4105	
lime- sandy	4205	
lime	4468	
lime & shale	4520	
lime	4525	
Mississippian Chert	4536	
Mississippi & Dolomite	4569	
Mississippian	4625	
Gilmore City	4645	RTD
Total Depth		

TOPS: LOG

Base Blaine	858
Anhydrite	1467
Heebner	3850
Lansing	3906
Marmaton	4281
Fort Scott	4439
Mississippi	4525
Gilmore City	4628