

19-22-22W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- PICKRELL DRILLING  
Farm- Miller No. 3

SEC. 19 T. 22 R. 22 W  
C NW NW

Total Depth. 4600'  
Comm. 7-2-63 Comp. 7-16-63  
Shot or Treated.  
Contractor. Pickrell Drig.  
Issued. 11-30-63

County Hodgeman  
KANSAS



Elevation. 2318' RB

Production. 77 BOPD- NW

CASING:

8 5/8" 278' cem w/ 175 sx  
4 1/2" 4585' cem w/ 165 sx

Figures indicate Bottom of Formations.

clay & post rock	70	
shale & shells	150	
shale & shells, sandy	260	
sand rock	278	
shale	649	
red bed	950	
sand	1220	
shale & sand	1430	
shells & shale	1475	
anhydrite	1515	
shale & shells	1950	
lime & shale	2330	
lime	2895	
shale & lime	3915	
lime	4430	
lime & shale	4473	
lime	4535	
Mississippian	4548	
Mississippian Chert	4555	
lime & chert	4558	
Chert	4562	
Mississippian chert	4600	RTD
Total Depth		

TOPS: LOG

Heebner	3857
Lansing	3914
Marmaton	4389
Mississippi	4532