

21-22-22W

Company- SUNRAY DX OIL CO.

SEC.

21

T. 22

R. 22W

Farm- Edwin Miller

No. 2

C SW NE

Total Depth. 4871'

Comm. 9/10/62 Comp. 9/28/62


Shot or Treated.

Contractor. Stickle Drilling Company

Issued. 3-23-63

County Hodgeman

KANSAS



CASING:
8" 267 Cem w/200 sacks
5" 4712

Elevation. 2216 RB

Production. 134 BOPD NW

Figures Indicate Bottom of Formations.

Shale and sand	50
Surface clay	250
blue shale	268
shale	370
shale and sand	1140
shale	1480
shale and red bed	1860
shale	2323
lime and shale	2445
shale and lime	2530
lime	2733
shale and sand	2805
lime and shale	2845
shale and chalk	3060
shale	3506
shale w/broken lime	3750
shale and lime	3870
lime and shale	3927
lime	4047
lime and chalk	4148
lime and shale	4294
shale and lime	4343
lime	4385
lime and chert	4470
lime and shale	4507
shale and chert	4557
lime	4578
lime and chert	4680
lime	4743
chert and lime	4752
lime and chert	4776
lime, chert and sand	4803
lime	4871
Total Depth	

TOPS: LOG

Heebner	3739
Lansing	3798
Base Kansas City	4100
Marmaton	4172
Fort Scott	4259
Cherokee	4319
Mississippi Osage	4407
Viola	4524
Simpson	4747
Arbuckle	4766