

25-22-22W

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **PICKRELL DRILLING**


SEC. 25 - T. 22 N. R. 22W

FARM **Ruff "A"** NO. **1**

LOC. **C SE NW**

TOTAL DEPTH **4515'**
 COMM. **8-30-68** COMP. **9-8-68**
 SHOT OR TREATED
 CONTRACTOR **Pickrell Drilling**
 ISSUED **11-16-68**

COUNTY **Hodgeman**



CASING

20	10	
15	8	5/8" 280' cem w/ 160 sx
12	6	
13	5	1/2" 4506' cem w/ 150 sx

ELEVATION **2251' KB**

PRODUCTION **PMP 101 BOPD PLUS**
Tr W/ Miss 4506-15 Or 35.6

FIGURES INDICATE BOTTOM OF FORMATIONS

20	Post rock
280	Shale & Sand Streaks
560	Shale & Red Bed
748	Shale & Shells
764	Blain
850	Shale & Shells
1040	Sand
1396	Shale & Shells
1430	Anhydrite
1730	Shale & Shells & Lime Streaks
2530	Lime & Shale
2785	Lime
3700	Lime & Shale
4503	Lime
4515	Chert

C. F. S.
 4445'
 4515'

Slope Tests
 2000
 2500
 3000
 4000

S. L. M.

Board 4097.01...
 Strap 4095.71
 Difference 1.30 short

TOPS: LOG	
Anhydrite	1396
Heebner	3834
Lansing Kansas City	3895
Fort Scott	4426
Cherokee shale	4450
Mississippi	4501
Ltd	4515