

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

26-22-22W

Company- IMPERIAL OIL COMPANY

Farm- Hann "D"

No. 1

SEC. 26 T. 22 R. 22W
C NW SE

Total Depth. 4421'

Comm. 5-7-63

Comp. 5-17-63


Shot or Treated.

Contractor. Imperial Oil of Kansas

Issued. 9-28-63

County Hodgeman

KANSAS



Elevation. 2167' K B

Production. 59DOPD - NW

CASING:

3 5/8" 275 cem w/200 sx

5 1/2" 4417 cem w/ 150 sx

Figures Indicate Bottom of Formations.

sand & shale	650
anhydrite	662
shale & sand	1297
anhydrite	1335
shale & lime	3840
lime	4416
chert	4421 RTD
Total Depth	

TOPS: SMP

Anhydrite	1297
Heebner	3730
Toronto	3748
Douglas Lime	3792
Lansing	3874
Base Kansas City	4135
Cherokee Shale	4323
Conglomerate	4392
Osage	4416

DST#1 4378-4421' Op 1 1/2 hrs recoved 460'
 mud, 180' heavy oil mud, 120' oil. ICIP
 1360# 20 min, IF 96#, FF 364#, FBHP 1054
 # 20 min