


27- 22- 22W

SEC. 27 T. 22 R. 22W
C NW NW

County Hodgeman
KANSAS



Elevation. 2202' KB

Production. 81 BOPD, NW

sand & shale	257
Anhydrite	720
sand	1000
shale & shells	1342
Anhydrite	1383
shale & shells	2150
lime & shale	3815
lime	4450
lime & Chert	4458 RTD
Total Depth	

Anhydrite	1342
Base Anhydrite	1383
Heebner Shale	3778
Toronto Lime	3797
Douglas Lime	3840
Lansing	3863
Base Kansas City	4179
Cherokee Shale	4361
Mississippi Osage	4450

DST #1 4417-54' Op 30 min. Weak
blow for 5 min. Tec. 15' mud w/specks
of oil. ICIP 1389#, IF 38#, FF 38#,
FCIP 1271#/20 min.

DST #2 Op 1 hr. Very strong flow throughout test. Rec. 2064' oil. ICIP 1360#, IF 307#, FF 781#, FCIP 1163#/20 min.