

30-22-22W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PICKRELL DRILLING
Farm- Housman "C" No. 1

SEC. 30 T. 22 R. 22W
C NW SE

Total Depth. 4593'
Comm. 3-5-64 Comp. 3-17-64
Shot or Treated.
Contractor. Pickrell Drilling.
Issued. 7-4-64

County Hodgeman
KANSAS



CASING:

Elevation. 2327' RB

8 5/8" 274' cem w/ 170 sx

Production. DRY

Figures Indicate Bottom of Formations.

P ost rock	75
shale & shells	620
red beds & shale	775
red beds	855
Blaine	870
Red Beds, shale & shells	950
sand	1165
shale & shells	1475
Anhydrite	1510
shale & shells	2070
lime & shale	2130
shale & lime, shells	2270
lime & shale	2430
lime	2790
lime & shale	2860
lime	2950
lime & shale	3705
sandy lime & shale	3735
lime & shale	3755
shale, sand & lime	3825
lime & shale	3956
lime	4095
lime & shale	4140
lime	4406
lime & shale	4507
lime	4517
lime & shale	4557
Conglomerate	4571
Mississippian	4583
Mississippian chert	4593 RTD
Total Depth	

TOPS: SMP

Heebner	3883
Lansing	3944
Marmaton	4334
Fort Scott	4479
Mississippi	4571