

31- 22. 22W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL COMPANY
Farm- Glunt No. 1

SEC. 31 T. 22 R. 22W
C SW NE

Total Depth. 4530'
Comm. 8-10-62 Comp. 8-23-62
Shot or Treated.
Contractor.
Issued. 11-10-62

County Hodgeman
KANSAS



CASING:
8 5/8" 260' cem w/200 sx.

Elevation. 2223' KB

Production. DRY

Figures indicate Bottom of Formations.

shale & sand	210
shale & shell	260
shale & sand	1385
anhydrite	1425
sand & shale	1810
shale & shells	2286
shale & lime	3640
lime	3770
lime & shale	3850
lime	4410
lime & shale	4434
lime	4480
lime & chert	4502
lime	4530 RTD
Total Depth	

TOPS: SAMPLE

Anhydrite	1380
Heebner	3792
Toronto	3809
Douglas Lime	3850
Lansing	3870
Cherokee Shale	4380
Conglomerate Shale	4463
Warsaw	4490
Osage	4503

- 1425 Base Anhydrite

DST #1 4444-4502' Op 30 min. Rec. 130'
watery mud. ICI 1961#/20 min. IF 97#
FF 127# BHP 1769#/20 min.