

34-22-224


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL COMPANY
Farm- McClean No. 1

SEC. 34 T. 22 R. 22W
C SW SW

Total Depth. 4427'
Comm. 1-22-65 Comp. 2-3-65
Shot or Treated.
Contractor. Imperial Oil of Kansas
Issued. 3-20-65

County Hodgeman
KANSAS



Elevation. 2174 KB

Production. Dry

CASING:

3 5/8" 315' cem w/250 sx.

Figures indicate Bottom of Formations.

sand & shale	315
shale	360
shale & red bed	770
water - sand	950
shale & shells	1308
Anhydrite	1339
red bed & shale	1905
lime & shale	2990
shale & lime	3108
lime & shale	3766
lime	4423
chert	4427
Total Depth	4427

TOPS: Log

*Anhydrite	1308
Heebner	3742
Toronto	3757
*Lansing	3805
Marmaton (Hanston zone)	4200
Cherokee shale	4329
Warsaw dolomite	4416
Osage chert	4419
Basal Pennsylvania sand	4407
*Mississippi Osage	4418

*Sample tops

DST # 1 4370-4423' Op 2 hrs. Weak blow.
increasing to strong blow. Rec. 250'
SOCM, ICIP 1399#, IFP 19#, FFP 105#, FCIP
1379# 20 min.

DST #2 4415-27 Op 1 hr. ^Very strong blow.
Rec. 60' SOCM, 10' free oil, 300' SOCMW
ICIP 1399#, IFP 57#, FFP 153#, FCIP 1379#
20 min.