



# K. G. S. LIBRARY

Basal Penn Sand 4407 (-2233)

4407-10 Green shaley glauconitic sand. Generally poor to fair porosity. No oil show.

Warsaw Dolomite 4416 (-2242)

4416-19 White and light gray finely crystalline to sucrosic dolomite with white to light gray opaque chert. Poor visible porosity. No oil show.

Osage Chert 4419-(-2245)

4419-27 White to light gray sharp to tripolitic opaque chert scattered fair vugular porosity and fair to good show of free oil.

DST #1

4370-4423

Open 2 hours. Weak blow. increasing to strong blow. Rec. 250' S.O.C.M., ICIP 1399#, IFP 19#, FFP 105#, FCIP 1379#/20".

DST #2

4415-27


Open 1 hour. Very strong blow. Rec. 60' S.O.C.M., 10' free oil, 300' S.O.C.W. ICIP 1399#, IFP 57#, FFP 153#, FCIP 1379#/20".

RTD

4427

The #1 McClean was judged to be non-commercial, and was plugged and abandoned February 3, 1965.

IMPERIAL OIL COMPANY

  
William A. Sladek  
Geologist