

SHALL WOOD

Form 113 50M 10-48-45767-D

State Kansas County Stafford

Sec. 22 Twp. 22 Rng. 14 W Elev. 1939'

Company R. L. Williams

Well No. 1 Name Prichard

Location 100 100 100

Feet from lines: N. S. E. W.

Spud 11-5-48 Completed 1-19-49

T. D. 3850' Casing 5" 3843

Comp. Perf.

Pay

I. P. D & A

Choke T. P. C. P.

G. O. R. Grvty.

DATE	REMARKS
1-19-49	Top 3120 Brn. Ln. 3145 Lns. 3156 G. Scl. 3711 Viola 3759 Simplish 3784 Simp. 384 3829 Arb. 3837. 80 3462-70 & 3483.

COMPLETION

DATE	REMARKS
	87. DST 3479-88 open 25 mins.
	rec. 300' oil & gas cut mud.
	LMP 1200. DST 3494-3505 open
	1/2 hr. rec. 100' gasy mud &
	60' oil cut mud. DST 3634-44
	open 30 mins. rec. 20' oil
	cut mud. DST 3573-3600 open
	30 mins. rec. 20' mud. BS. DST
	3603-83 open 30 mins. rec. 90'
	mud. BS. DP TO 3850. RFW. LMP
	3724. 12 # 3487-90. show free
	oil on gun. 250 A. 8 # 3455-
	87. 5000 A. Swb. 4 BPH 18
	hr. Swb. 216 BPH. 50% oil.
	Swb. 4 BPH 2/3 wtr. Re-perf.
	3481-85 w/16 #. No inc. LMP
	3473. 24 # 3460-68. 6 # 3470-
	72. DP 3473. 24 # 3640-44.
	6 # 3638-40. 6 # 3644-46.
	Packer at 3600. 500 A. Swb.
	oil & wtr. 1000 A. Swb. est. 5
	BPH no wtr. 8 hr. 600 butane.
	4000 A. Swb. 40 BO 5 hr. Dec. to
	zero. Then swb. 3/4 BO & 4 BPH
	3460-90. Sqrd. all perfe. 24 #
	3616-24. CO. VSSO. 1000 A. Swb.
	4 BPH & Seum oil. LMP 3544.
	51 # 3524-36. B/10 BPH. LMP
	3513. 88 # 3498-3507. SSO. 500 A.
	Swb. 1 BPH. 90% wtr. 1000 A. Swb.
	5 BPH. 90% wtr.
	COMPLETE

22652