

OCT 25 1969

WELL LOG

2-22-23W

Chief Drilling Co. Inc.
905 Century Plaza
Wichita, Kansas 67202

#1 EWY
C SW SW Sec. 2-22-23W
Hodgeman County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 9-11-69
Completed: 9-21-69

Casing Record: Set 332' of 8 5/8" @10:30 P.M. on
9-11-69 w/225 sacks common 1% Gel.


Dry

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
			2308 Gr.
			2310 D.F.
			2313 K.B.
Surface clay and sand	0	50	
Shale	50	342	
Sand & shale	342	1385	
Red bed & shale	1385	1517	
Anhydrite	1517	1553	
Shale & shells	1553	1946	
Shale, shells, lime strks.	1946	2093	
Shale & Lime	2093	2660	
Lime	2660	2830	
Lime & shale	2830	4095	
Lime	4095	4115	
Lime & shale	4115	4270	
Lime	4270	4650	
Total depth	4650		

FORMATION TOPS

Anhydrite	1517 + 796
Heebner	3881 -1568
Toronto	3900 -1587
Lansing	3937 -1624
T.D.	4650 -2337

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:



I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C SW SW of Section 2-2-23W, Hodgeman County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson
Jim Robinson, Office Mgr.

Subscribed and sworn to before me this 25th day of September, 1969.



EXPIRES:

Betty Brandt
Betty Brandt, Notary Public