

IMPORTANT
Kans. Geo. Survey request
samples on this well.

API No. 15 — 083 — 20,346
County Number

Operator

Petroleum, Inc.

Address 300 West Douglas
Wichita, Kansas 67202

Well No.

#1

Lease Name

Campbell "Q"

Footage Location

1980 feet from XX (S) line

660 feet from (E) XX line

Principal Contractor

DaMac Drilling Co.

Geologist

Raymond M. Goodin

Spud Date

December 14, 1973

Total Depth

RTD 4654

P.B.T.D.

Date Completed

December 28, 1973


Oil Purchaser

S. 5 T. 22 R. 23 E
W

Loc. C NE SE

County Hodgeman

640 Acres
N



Locate well correctly

Elev.: Gr. 2341'

DF 2344' KB 2346'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	477'	Regular	275	3% CC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at			


ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS		Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)				Producing interval (s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Petroleum, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole	
Well No. 1	Lease Name CAMPBELL '0'		
S <u>5</u> T <u>22</u> S R <u>23</u> W ^E C. NE SE			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
DST #1: 4570-4602: 30-30-30-60; recovered 45' oil cut mud; 1FP 18#-23#, 1BHP 1198#, 2FP 35#-47#, 2BHP 1314# DST #2: 4599-4608: 30-30-15-30; weak 25" blow; 15' mud; 1FP 27#-23#, 1BHP 23#, 2FP 23#-23#, 2BHP 23# DST #3: 4599-4614: 30-30-15-30; weak blow; 5' mud; FP 5#-5#, BHP 10#-10# DST #4: 4618-4641: 30-30-15-30; weak blow; 5' mud; FP 14#-14#, BHP 47#-119#			Dresser Atlas CR-N-LL & BHC AL E.L. TOPS: Anhydrite 1610 Heebner 3917 Toronto 3935 Lansing 3971 Stark 4234 Hertha 4284 BKC 4345 Pawnee 4443 Fort Scott 4504 Mississippi 4586 ELTD 4654
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Jay C. McNeil District Geologist January 8, 1974		
	Signature Title Date		