

IMPORTANT
Kans. Geo. Survey request
samples on this well.

API No. 15 — 083 — 20,351 20351
County Number

Operator

Petroleum, Inc.

Address 300 West Douglas
Wichita, Kansas 67202

Well No.

#1

Lease Name

Goebel "H"

Footage Location

1890 feet from ~~XX~~ (S) line 750 feet from ~~XX~~ (W) line

Principal Contractor

Strata Drilling Inc.

Geologist

Deane Jirrels

Spud Date

1-31-74

Total Depth

RTD 4700'

P.B.T.D.

Date Completed

2-10-74


Oil Purchaser

S. 6 T. 22 R. 23 ~~X~~ W

Loc. A/NW SW

County Hodgeman

640 Acres



Locate well correctly

Elev.: Gr. 2394

DF 2397 KB 2399

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	399'	Common	250	2% Gel, 3% CC

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement
----------	-------------	--------------

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
---------------	-------------	----------------

TUBING RECORD

Size	Setting depth	Packer set at
------	---------------	---------------

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Petroleum, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole	
Well No. 1	Lease Name GOEBEL 'H'		
S 6 T 22 R 23W^E A/C NW SW			
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
DST #1: 4590-4645: 30-30-30-60; weak steady blow; 50' mud w/few specks oil; 1FP 69#-81#, 1BHP 1263#, 2FP 81#-92#, 2BHP 1285# DST #2: 4645-55: misrun DST #3: 4614-55: 30-30-30-60; weak blow; 20' mud, 1FP 58#-69#, 1BHP 104#, 2FP 69#-81#, 2BHP 104# DST #4: 4614-75; 30-30-30-60; weak blow; 25' mud; 1FP 81#- 92#, 1BHP 207#, 2FP 92#-104#, 2BHP 184#			Dresser Atlas LL-GR-N Log Tops: Anhydrite 1680 Heebner 3960 Toronto 3976 Lansing 4013 Stark 4274 Hertha 4316 BKC 4388 Marmaton 4420 Pawnee 4491 Fort Scott 4547 Cherokee 4572 Mississippi 4640 ELTD 4700
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
152345078 Date Received	 Jay C. McNeil District Geologist		
	Signature Title 2-21-74 Date		