

Well No. 1	Lease Name Bamberger
S 10 T 22 R 23 E W Hodgeman Co., Ks.	

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 - 4574-4603' 30(30)30(60). Strong blow throughout. Rec. 1140' GIP; 630' gassy oil (gravity 32°); 300' very heavy oil & gas cut mud, 90% oil, 5% mud, 5% gas Hyd. 2255 & 2243# FPS. 91-264 & 306-380# SIPS 1358 & 1375# DST #2 - 4603-13, 30(30)30(60) Strong blow throughout. Rec. 1620' GIP, 1440' clean gassy oil - gravity 33° Hyd. 2258 & 2253# FPS. 157-372 & 430 - 555# SIPS. 1273 & 1324# Temp 116°			Electric Log	
			Anhyd	1580 + 788
		Heebner	3916 - 1548	
		Lansing	3967 - 1599	
		B/KC	4344 - 1976	
		Ft. Scott	4504 - 2135	
		Miss. (W)	4598 - 2230	
		Miss. (O)	4608 - 2240	
		LTD	4649 - 2281	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>Ronald J. Schmitt</i>
	Signature
	Operations Manager
	Title
	January 30, 1981
	Date