

15-22-23W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- RAINS & WILLIAMSON OIL CO. ETAL
Farm- Armstrong No. 1

SEC. 15 T. 22 R. 23W
C SW SE

Total Depth. 4585'
Comm. 8-14-63 Comp. 8-26-63
Shot or Treated.
Contractor.
Issued. 1-18-64

County Hodgeman
KANSAS



Elevation. 2327' RB

Production. 61 BOPD, 40% WTR.

CASING:

8 5/8" 287' cem w/175 sx.
4" 4580' cem w/75 sx.

Figures Indicate Bottom of Formations.

shale	450
sand	490
shale & redbed	925
Anhydrite	940
shale	1015
D. sand	1230
shale & redbed	1545
Anhydrite	1575
shale & shells	2475
shale & lime	2700
lime & shale	3440
shale & lime	3930
lime & shale	4100
lime	4565
lime & chert	4580
lime	4585 RTD
Total Depth	

TOPS: LOG

Bl. Anhydrite (sample)	925
Cim. Anhydrite "	1540
Heebner	3882
Toronto	3898
Lansing	3939
Base Kansas City	4245
Marmaton	4314
Marmaton Zone	4334
Ft. Scott	4413
Cherokee	4471
Weakened Mississippi	4548
Mississippi	4568