

17-22-23W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- TENNESSEE GAS TRANSMISSION CO.
Farm- Novotny No. 1

SEC. 17 T. 22 R. 23W
 SW SE NW

Total Depth. 4659'
Comm. 8-3-59 Comp. 8-23-59
Shot or Treated.
Contractor. Pickrell Drlg.
Issued. 12-5-59

County Hodgeman
 KANSAS



CASING:
8 5/8" 216' cem w/235 sx.
5 1/2" 4658½' cem w/130 sx.

Elevation. 2387' RB

Production. 3000 BOPD

Figures Indicate Bottom of Formations.

Meas. from top of RB.

clay & shale	320
red rock & shale	900
red bed, shale & shells	1470
shale & shells	2185
shale & lime	2605
lime	3120
lime & shale	4010
lime	4022
lime & shale	4210
cherty lime & shale	4255
lime	4515
lime & shale	4625
Mississippi	4659
Total Depth	

TOPS:
Anhydrite 1632
Heebner 3927
Lansing 4003
Marmaton 4374
Mississippi 4622

Core #1 4625-43' Full recovery
Core #2 4644-58½' Full recovery

DST #1 4634-59', op 2 hrs., op w/good blow,
died in 1 hr 10 min; rec. 4002' oil
(Reversed out 3821' oil and 179' VHOCM).
BHP 1455/29", IFP 325#, FFP 1440#, FBHP
1440#/60".