

TYPE

CONFIDENTIAL

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

18-22-23W

Compt. _____

SIDE ONE

(Rules 82-3-130 and 82-3-107)

This form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ninety (90) days after the completion of a well, regardless of how the well was completed.

State Geological Survey
WICHITA BRANCH

DOCKET NO. NP _____

FOR INFORMATION REGARDING THE NUMBER OF COPIES TO BE FILED AND APPLICATIONS REQUIRING COPIES OF ACO-1 FORMS SEE PAGE TWO (2), SIDE TWO (2) OF THIS FORM.

☒ Letter requesting confidentiality attached.

☒ Attach ONE COPY of EACH wireline log run (i.e. electrical log, sonic log, gamma ray neutron log etc.)***Check here if NO logs were run _____.

PLEASE FILL IN ALL INFORMATION. IF NOT AVAILABLE, INDICATE. IF INFORMATION LATER BECOMES AVAILABLE, SUBMIT BY LETTER.

LICENSE # 5399 EXPIRATION DATE 7/1/84

OPERATOR American Energies Corporation API NO. 15-083-21,111

ADDRESS 575 Fourth Financial Center COUNTY Hodgeman

Wichita, Kansas 67202 FIELD Wildcat

** CONTACT PERSON Jim Hall PROD. FORMATION N/A
PHONE (316) 263-5785 N/A Indicate if new pay.

PURCHASER N/A LEASE Reed

ADDRESS _____ WELL NO. 1

WELL LOCATION C NW NW

DRILLING White & Ellis Drilling, Inc. 660 Ft. from North Line and

CONTRACTOR 5532 W. 10th 660 Ft. from West Line of

ADDRESS Great Bend, Kansas 67530 the NW (Qtr.) SEC 18 TWP 22S RGE 23W (E) (W)

PLUGGING Same as Drilling Contractor WELL PLAT (Office Use Only)
CONTRACTOR _____
ADDRESS _____

TOTAL DEPTH 4732' PBTD _____

SPUD DATE 1/17/84 DATE COMPLETED 1/30/84

ELEV: GR 2422' DF 2424' KB 2427'

DRILLED WITH ~~(CABLE)~~ (ROTARY) ~~(AIR)~~ TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE N/A

Amount of surface pipe set and cemented 405' DV Tool Used? No


TYPE OF COMPLETION THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Shut-in Gas, Gas, Dry, Disposal, Injection, Temporarily Abandoned. If OWWO, indicate type of re-completion _____. Other completion _____. NGPA filing _____.

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

I, Van F. Griffin, being of lawful age, hereby certifies at:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit.



WEC - 22 - 81

ACQ-1, Well History

Side TWO

OPERATOR American Energies Corp. LEASE NAME Reed

SEC 18 TWP 22 S RGE 23W (E)

WELL NO 1

FILL IN WELL INFORMATION AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

Show Geological markers, logs run, or other Descriptive information.

Formation description, contents, etc.	Top	Bottom	Name	Depth
Check if no Drill Stem Tests Run. Check if samples sent Geological Survey. DST #1 4658-4715', 40/30/30/30, IH 2436, IF 55-55, dec'd. 16", flush no help, IS 98, FF 55-55, FS 87, FH 2415, rec. 30' SOSM. DST #2 4709-4725', 30/45/60/90, DoIo. fair show free oil, vuggy $\emptyset$, IH 2511, IF 33-33, IS 1447, FF 44-44, FS 1447, FH 2489, rec. 10' CGO, 37° & 70° + 51' OCM. DST #3 4718-4732', 30/45/60/90, IH 2521, IF 55-87, IS 1447, FF 142-218, FH 1447, rec. 484' TF (1.5' CO + 112' SOCMW + 10% O, 50% M, 40% W + 186' VSOCMW, 50% O, 10% M, 85% W + 186' VSOCW, 5% O, 95% W, RTD 4732'. E-Log Tops: Anhydrite +737 Heebner -1572 Lansing -1619 B/KC -2007 Fort Scott -2165 Cherokee -2194 Mississippi -2273 TD -2305 If additional space is needed use Page 2				

Report of all strings set — surface, intermediate, production, etc.

CASING RECORD (New) or ~~Used~~

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"		412'	60/40 POZ	220	2% gel 3% CC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD					
Size	Setting depth	Packer set at			