

26-22-23W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. BIRMINGHAM-BARTLETT DRILLING CO.
Farm. Jensen No. 1

SEC. 26 T. 22 R. 23W
150' S OF C SE SE

Total Depth. 4509'
Comm. 10-30-63 Comp. 11-17-63
Shot or Treated.
Contractor. Birmingham -Bartlett Drlg.
Issued. 3-21-64

County Hodgeman
KANSAS



Elevation. 2260' RB

Production. 39 BOPD, 42% WTR.

CASING:

8 5/8" 240' cem w/185 sx.
5 1/2" 4504' cem w/100 sx.

Figures Indicate Bottom of Formations.

clay sand	100
shale	210
shale & shells	310
shale	800
Blaine anhydrite	814
shale	900
sand	1100
shale	1165
shale & redbed	1427
s.c. Anhydrite	1457
shale & shells	2230
lime & shale	2590
lime	2700
lime & shale	3736
lime	3799
lime & shale	3830
lime	4347
lime & shale	4394
Fort Scott	4410
lime	4457
lime & shale	4475
Mississippi Warsaw	4497
Lime	4509 RTD
Total Depth	

DST #1 4456-97' Op 1 3/4 hrs., Rec. 62' slightly oil cut mud. IBHP 338#, FBHP 117#, FP'S 23 & 39#.

DST #2 4496-4501' Op 70", Rec. 30' very slightly oil cut mud, BHP 605#, & 769#, FPs 4# & 15#.

DST #3 4491-4504' Op 60", Rec. 30' mud. BHP 870# & 800#, FPs 15# & 26#.

DST #4 4496-4509' Op 90", Rec. 100' slightly oil cut mud, IBHP 1413#, FBHP 1379#, FPs 39# & 62#.

TOPS: LOG

Base Blaine Anhydrite	811
Top Cedar Hills Sandstone	891
Base Cedar Hills Sandstone	1080
Top Stone Corral Anhydrite	1423
Heebner	3794
Lansing	3854
Marmaton	4238
Fort Scott	4327
Cherokee Limestone	4393
Conglomerate	4457
Top Mississippi, Warsaw	4475
Top Mississippi, Osage	4494 (4498)