

36-22-23W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL COMPANY
Farm- Billings No. 1

SEC. 36 T. 22 R. 23W
C NE NW

Total Depth. 4512'
Comm. 7-26-62 Comp. 8-10-62
Shot or Treated.
Contractor.
Issued. 12-1-62

County Hodgeman
KANSAS



Elevation. 2263' KB

Production. 241 BOPD, TR WTR.

CASING:

8 5/8" 279' cem w/200 sx.
5 1/2" 4500' cem w/125 sx.

Figures Indicate Bottom of Formations.

shale & sand	1417
Anhydrite	1454
shale & shells	2230
lime & shale	3838
lime	4145
lime & shale	4275
lime	4475
chert & lime	4512 RTD
Total Depth	

TOPS:	SAMPLE	ELECTRIC
Anhydrite	1417	1415
Heebner	3788	3789
Toronto	3807	3804
Douglas Lime (L-1)	3849	3845
Lansing (L-2)	3866	3864
Base Kansas City	4190	4186
Cherokee Shale	4376	4374
Conglomerate Shale	4449	4446
Warsaw Dolomite	4476	4473
Osage	4482	4479

DST #1 4428-4475' Op ½ hr. Rec. 5' mud.
ICIP 0#/20 min. IF 0# FF 0# FBHP 0#/20 min.

DST #2 4477-4483' Op 2 hrs. Rec. 125'
heavily oil cut mud. ICIP 1310#/20 min.
IF 0# FF 48# FBHP 1025#/20 min.

DST #3 4483-4495' Plugged tool.

DST #4 4483-4498' Op 2 hrs. Rec. 3500'
clean gassy oil. ICIP 1379#/20 min.
IF 1015# FF 1310# FBHP 1350#/20 min.

DST #5 4499-4512' Op 1½ hrs. Rec. 3550'
clean gassy oil. ICIP 1369#/20 min. IF 966#
FF 1310# FBHP 1330#/20 min.