


15-083-21576

29-22s-23w

IND



**TRILOBITE
TESTING, INC.**

CONFIDENTIAL

JAN 07 2009

KCC

DRILL STEM TEST REPORT

Prepared For: **American Warrior Inc.**

PO Box 399
Garden City Ks, 67946

ATTN: Jason Alm

29 22 23 Hodgeman KS

Sprier Unit #1-29

Start Date: 2008.11.22 @ 11:05:52

End Date: 2008.11.22 @ 18:27:37

Job Ticket #: 30813 DST #: 1

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 08 2009
CONSERVATION DIVISION
WICHITA, KS

Trilobite Testing, Inc

PO Box 1733 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620

American Warrior Inc.


Sprier Unit #1-29

29 22 23 Hodgeman KS

DST # 1

Osage

2008.11.22



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

American Warrior Inc.

PO Box 399
Garden City Ks, 67946

ATTN: Jason Alm

Sprier Unit #1-29

29 22 23 Hodgeman KS

Job Ticket: 30813

DST#: 1

Test Start: 2008.11.22 @ 11:05:52

GENERAL INFORMATION:

Formation: **Osage**

Deviated: **No** Whipstock: **ft (KB)**

Time Tool Opened: 13:31:52

Time Test Ended: 18:27:37

Test Type: Conventional Bottom Hole

Tester: Mike Slomp

Unit No: 28

Interval: **4588.00 ft (KB) To 4608.00 ft (KB) (TVD)**

Total Depth: 4608.00 ft (KB) (TVD)

Hole Diameter: 7.78 inches Hole Condition: Fair

Reference Elevations: 2315.00 ft (KB)

2303.00 ft (CF)

KB to GR/CF: 12.00 ft

Serial #: 6752 Inside

Press@RunDepth: psig @ 4590.00 ft (KB)

Start Date: 2008.11.22

End Date:

2008.11.22

Start Time: 11:05:53

End Time:

18:27:37


Capacity: 7000.00 psig

Last Calib.: 2008.11.22

Time On Btm: 2008.11.22 @ 13:27:52

Time Off Btm: 2008.11.22 @ 14:02:52

TEST COMMENT: IF- Strong blow , BOB in 1 min
Tool would not turn to shut in , pulled tool



PRESSURE SUMMARY


Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	2284.42	112.07	Initial Hydro-static
4	284.96	134.52	Open To Flow (1)
33	799.85	140.67	Shut-In(1)
35	2199.86	134.08	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
2015.00	100%oil	28.27

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

American Warrior Inc.

PO Box 399
Garden City Ks, 67946

ATTN: Jason Alm

Sprier Unit #1-29

29 22 23 Hodgeman KS

Job Ticket: 30813

DST#: 1


Test Start: 2008.11.22 @ 11:05:52

Tool Information

Drill Pipe:	Length: 4573.00 ft	Diameter: 3.80 inches	Volume: 64.15 bbl	Tool Weight: 2000.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight set on Packer: 25000.00 lb
Drill Collar:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight to Pull Loose: lb
			Total Volume: 64.15 bbl	Tool Chased ft
Drill Pipe Above KB:	12.00 ft			String Weight: Initial lb
Depth to Top Packer:	4588.00 ft			Final lb
Depth to Bottom Packer:	ft			
Interval between Packers:	20.00 ft			
Tool Length:	47.00 ft			
Number of Packers:	2	Diameter: 6.75 inches		
Tool Comments:				

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			4562.00	
Shut In Tool	5.00			4567.00	
Hydraulic tool	5.00			4572.00	
Jars	5.00			4577.00	
Safety Joint	2.00			4579.00	
Packer	5.00		Fluid	4584.00	27.00 Bottom Of Top Packer
Packer	4.00			4588.00	
Perforations	1.00			4589.00	
Stubb	1.00			4590.00	
Recorder	0.00	6752	Inside	4590.00	
Recorder	0.00	8321	Inside	4590.00	
Perforations	15.00			4605.00	
Bullnose	3.00			4608.00	20.00 Bottom Packers & Anchor

Total Tool Length: 47.00



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

FLUID SUMMARY

American Warrior Inc.

Sprier Unit #1-29

PO Box 399
Garden City Ks, 67946

29 22 23 Hodgeman KS

ATTN: Jason Alm

Job Ticket: 30813

DST#: 1

Test Start: 2008.11.22 @ 11:05:52

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

41 deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

ppm

Viscosity: 56.00 sec/qt

Cushion Volume:

bbl

Water Loss: 8.76 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 3900.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
2015.00	100%oil	28.265

Total Length: 2015.00 ft Total Volume: 28.265 bbl

Num Fluid Samples: 0


Num Gas Bombs: 0

Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments: RW .41 @ 60F



233828