

KANSAS DRILLERS LOG

State Geological Survey
WICHITA, BRANCHAPI No. 15 — 083 — 20,473
County Number

S. 4 T. 22 R. 24 E W

Loc. 150' E/C NW SW

Operator

Patrick Petroleum Corp.

Address

Suite 414, 200 East First Wichita, Kansas 67202

Well No.

#1

Lease Name

Gumbir

Footage Location

1980

feet from (S) line

810

feet from (W) line

Principal Contractor

SLAWSON DRILG CO.

Geologist

RAYMOND GOODIN

Spud Date

MAY 29, 1976

Total Depth

4700


P.B.T.D.

Date Completed

JUNE 6, 1976

Oil Purchaser

County Hodgeman

640 Acres
N

Locate well correctly

Elev.: Gr.

2455

DF 2457 KB 2460

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE		8 5/8		491	60/40 Pcs. 2 1/2 yd. 3% G.	350	

LINE RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None	

INITIAL PRODUCTION

Date of first production None		Producing method (flowing, pumping, gas lift, etc.) —		
RATE OF PRODUCTION PER 24 HOURS	Oil — bbls.	Gas — MCF	Water — bbls.	Gas-oil ratio — CFPB
Disposition of gas (vented, used on lease or sold) —			Producing interval (s) —	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

operator Patrick Petroleum Corporation		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: DRY HOLE	
Well No. # 1	Lease Name GUMBIR		
S 4 T 22 R 24 W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	LOG NAME TOPS DEPTH
DST #1 4544 - 4640 30"-30"-10"-30" WB 10" Flushed on 1 st & 2 nd Rec 130' mud few oil spots ISHP 183 * FBHP 232 * IF 68 * FF 68 * Hydr 2312 - 2307 * Congl.	SPIC TOPS 4620	4640	Ab. Sh. Lansing Ft. St. Cherokee Congl. Miss
Cat. v. col., wht., yellow, Fresh op. tr. stain, fat. odor, few sand clusters oil stain			3446 (1486) 4004 (-1644) 4530 (-2074) 4558 (-2098) 4623 (-2163) 4642 (-2182)
Miss. dol. wat. gry. f.xln. dze. no f. n.s. sh. glauc. to. tr. x pov. - poor dol. aa. sh. inc. x vug. f. ns. glauc. dol. wat. gry. tan. f.xln. fr. qd. x vug. f. ns. wat glauc. dol. gry. tan. f.xln. fr-qd. x, vug. f. tr. op. gry. wt. Nso dr. gry., grn. tan f.xln fr-qd. x vug. f. tr. chr. + qtz some suc. x dol. do. gry. wat. f. x - suc. rpt. qd. x vug. f. Nso inc. chr. gry. wat. op. dol. wat. gry. inc. suc. x pov. f. chr. wat op.	4620	4640	
	4640	4650	
	4650	4660	
	4660	4670	
	4670	4680	
	4680	4690	
	4690	-4700	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<div style="text-align: right;"> <u>Michael Mitchell</u> <small>Signature</small> <u>Geologist Patrick Petroleum Corp.</u> <small>Title</small> <u>July 12, 1976</u> <small>Date</small> </div>
---------------	--

COMPANY: Patrick Petroleum Company
Suite 414, 200 East First Street
Wichita, Kansas 67202

LEASE NAME: Gumbir No.1
C NW SW 4-22-24W
Hodgeman County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
408 One Twenty Building
Wichita, Kansas 67202

TOTAL DEPTH: 4700'

COMMENCED: May 29, 1976

COMPLETED: June 6, 1976

CASING: 513.36' of new 8-5/8" set at 491' with 350 sx cement

0' to 320' Surface hole
320' to 496' Shale
496' to 1205' Shale & Shells
1205' to 1360' Sand
1360' to 1470' Shale & shells
1470' to 1687' Shale
1687' to 1721' Anhydrite
1721' to 2560' Shale & Shells
2560' to 4395' Lime and Shale
4395' to 4640' Lime
4640' Cong.
4640' to 4700' Lime
4700' RTD

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc.
upon oath state that the above and foregoing is a true and correct copy of the
log of the Gumbir No.1 well.


James C. Remsberg

Subscribed and sworn to me on June 10, 1976.

RECEIVED
STATE CORPORATION COMMISSION
SEP 26 1980
CONSERVATION DIVISION
Wichita, Kansas