

KANSAS DRILLERS LOG
State Geological SurveyWICHITA, BRANCH
API No. 15 083

County

IMPORTANT
Kans. Geo. Survey request
samples on this well.


20,312

Number

S. 5 T. 22 R. 24 E

Loc. C SW NE

County Hodgeman

640 Acres
N

Locate well correctly

Elev.: Gr. 2418'

DF 2420' KB 2422'

Operator

Petroleum, Inc.

Address 300 West Douglas
Wichita, Kansas

Well No.

#2

Lease Name

Boger "C"

Footage Location

1980 feet from (N) ☒ line1980 feet from (E) ☒ line

Principal Contractor

Strata Drilling Company

Geologist

H. Deane Jirrels

Spud Date

June 30, 1973

Total Depth

RTD 4600

P.B.T.D.

Date Completed

July 9, 1973

Oil Purchaser

-

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	405'	Common	225	2% Gel, 3% CC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Petroleum, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole																											
Well No. 2	Lease Name Boger 'C'																												
S <u>5</u> T <u>22</u> R <u>24</u> XX W C. SW NE																													
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.																											
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.																													
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 60%; padding: 2px;">NAME</th> <th style="width: 40%; padding: 2px;">DEPTH</th> </tr> </thead> <tbody> <tr> <td colspan="2" style="padding: 2px;">Dresser Atlas IL-G/R-N Tops:</td> </tr> <tr> <td style="padding: 2px;">Anhydrite</td> <td style="text-align: right; padding: 2px;">1631</td> </tr> <tr> <td style="padding: 2px;">Heebner</td> <td style="text-align: right; padding: 2px;">3871</td> </tr> <tr> <td style="padding: 2px;">Toronto</td> <td style="text-align: right; padding: 2px;">3891</td> </tr> <tr> <td style="padding: 2px;">Lansing</td> <td style="text-align: right; padding: 2px;">3924</td> </tr> <tr> <td style="padding: 2px;">BKG</td> <td style="text-align: right; padding: 2px;">4294</td> </tr> <tr> <td style="padding: 2px;">Marmaton</td> <td style="text-align: right; padding: 2px;">4322</td> </tr> <tr> <td style="padding: 2px;">Fort Scott</td> <td style="text-align: right; padding: 2px;">4444</td> </tr> <tr> <td style="padding: 2px;">Cherokee</td> <td style="text-align: right; padding: 2px;">4468</td> </tr> <tr> <td style="padding: 2px;">Mississippi dolo.</td> <td style="text-align: right; padding: 2px;">4538</td> </tr> <tr> <td style="padding: 2px;">Miss. Osage</td> <td style="text-align: right; padding: 2px;">4578</td> </tr> <tr> <td style="padding: 2px;">ELTD</td> <td style="text-align: right; padding: 2px;">4600</td> </tr> </tbody> </table>	NAME	DEPTH	Dresser Atlas IL-G/R-N Tops:		Anhydrite	1631	Heebner	3871	Toronto	3891	Lansing	3924	BKG	4294	Marmaton	4322	Fort Scott	4444	Cherokee	4468	Mississippi dolo.	4538	Miss. Osage	4578	ELTD	4600
NAME	DEPTH																												
Dresser Atlas IL-G/R-N Tops:																													
Anhydrite	1631																												
Heebner	3871																												
Toronto	3891																												
Lansing	3924																												
BKG	4294																												
Marmaton	4322																												
Fort Scott	4444																												
Cherokee	4468																												
Mississippi dolo.	4538																												
Miss. Osage	4578																												
ELTD	4600																												
DST #1: 4452-80: 30-30-45-30; very weak blow for 3 minutes; recovered 10' mud; 1FP 32#-32#, 1BHP 47#, 2FP 40#-40#, 2BHP 45# DST #2: 4490-4550: 30-30-30-30; weak blow for 5 minutes; recovered 10' mud; 1FP 23#-23#, 1BHP 51#, 2FP 31#-36#, 2BHP 49# DST #3: 4488-4560: 30-30-30-30; weak blow for 30", no blow on 2nd flow; recovered 20' mud w/spots of oil; 1FP 37#-39#, 1BHP 821#, pressures not recorded on 2F and 2BH--clock stopped DST #4: 4549-68: 30-30-30-30; weak blow for 15 minutes, no blow on 2nd flow; recovered 20' mud w/scum of oil; 1FP 36#-36#, 1BHP 1136#, 2FP 42#-46#, 2BHP 1100#																													
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.																													
<div style="border: 2px solid black; border-radius: 50%; width: 150px; height: 150px; display: flex; align-items: center; justify-content: center; margin: 0 auto;"> <div style="text-align: center;"> <p>Date Received AUG 1973</p> <p>RECEIVED</p> <p>STATE GEOLOGICAL SURVEY OF KANSAS</p> </div> </div>	<div style="margin-bottom: 10px;"> <div style="text-align: center;">Signature</div> </div> <div style="margin-bottom: 10px;"> <div style="text-align: center;">District Geologist</div> <div style="text-align: center;">Title</div> </div> <div> <div style="text-align: center;">August 8, 1973</div> <div style="text-align: center;">Date</div> </div>																												