


WELL LOG

8-22-246



NOV 19 1971

COMPANY

Petroleum, Inc.

SEC. 8 T. 22S R. 24W

FARM

Smith 'AR'

NO. 1

LOC. App. NW NW

TOTAL DEPTH

4580'

COUNTY Hodgeman, Kansas


COMM.

8-28-71

COMP. 9-7-71

CONTRACTOR

Garvey Drilling Company



CASING

8 5/8" @ 446' w/225sx

5 1/2" @ 4578' w/75 sx

ELEVATION 2446 DF

PRODUCTION

100 Gopp 20% wt
MISSISSIPPI

FIGURES INDICATE BOTTOM OF FORMATIONS

Log Tops

A hy
n
HeeB
Lans
Ft Sc
Miss
RTD

1638
3868
3922
4453
4552
4580

105' Surface Soil & Shale
447' Sand & Shale
875' Shale & Red Bed
1040' Blaine Anhydrite
1125' Shale & Red Bed
1315' Sand
1615' Shale
1677' Anhydrite
2035' Shale & Shells
2490' Shale & Lime
2600' Lime & Shale
3010' Lime
3753' Lime & Shale
3915' Lime
4580' Lime
4580' RTD