

State Geological Survey
WICHITA, BRANCH

MAR 07 1977

KANSAS DRILLERS LOG

API No. 15 — 083 — 20495
County Number

Operator
Petroleum, Inc.

Address
800 R.H. Garvey Bldg., 300 W. Douglas, Wichita, Ks. 67202

Well No. 6 Lease Name Springer

Footage Location
660 feet from ~~XXX~~ (S) line 660 feet from (E) ~~XXX~~ line

Principal Contractor B & B Drlg. Inc. Geologist Jim Reeves


Spud Date 9-29 Total Depth 4652' P.B.T.D.

Date Completed 10-16-76 Oil Purchaser Skelly Oil Company

S. 23 T. 22S R. 24 ^{EX}_W
Loc. C. SE. SE.

County Hodgeman

640 Acres
N



Elev.: Gr. 2411

DF 2413 KB 2416

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8	20#	405'	Common	225	2% gel, 3% c.c.
Production	7-7/8"	5 1/2"	15.5# 14#	4653'	50/50 Pozmix	100	10% salt W/FRA

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
2	DP Jets	4617-26'

TUBING RECORD

Size	Setting depth	Packer set at
2-3/8" OD EUE	4592	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None	

INITIAL PRODUCTION

Date of first production <u>Nov. 4, 1976</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Pumping</u>				
RATE OF PRODUCTION PER 24 HOURS	Oil <u>31</u> bbls.	Gas <u>-</u> MCF	Water <u>Trace</u> bbls.	Gas-oil ratio <u>-</u>	CFPB
Disposition of gas (vented, used on lease or sold) <u>-</u>			Producing interval (s) <u>24 hr.</u>		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Petroleum, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 6	Lease Name Springer	Oil
S <u>23</u> T <u>22</u> R <u>24</u> W ^{EX} _W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 4619-4625 30-60-30-60 Strg blow, 180' gas, 1235' free oil, 310, 180' muddy oil, 25% mud. IHP 2515, IF 173-254, ISI 1108, FF 346-551, FSI 842 FHP 2493.			E.L. TOPS Anh. 1640 (+776) B/Anh. 1670 (+746) Hbn. 3932 (-1516) Lans. 3986 (-1570) B/KC 4368 (-1952) Marm. 4381 (-1965) Ft.Sc. 4524 (-2108) Cke.Sh. 4550 (-2134) Miss. 4614 (-2198) LTD 4654	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>R. H. Duncanson</i>
	Signature
	Office Manager
	Title
	Nov 26, 1976
	Date