

24-22-24W

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **LEBEN DRILLING, INC. ET AL**


SEC. 24 T. 22 R. 24W
LOC. 150' S of C SE SE

FARM **Springer "A"** NO. **1**

TOTAL DEPTH **4620'**
COMM. **10-27-67** COMP. **11-7-67**
SHOT OR TREATED
CONTRACTOR **Beben D. Ig., Inc.**
ISSUED **12-16-67**

COUNTY **Hodgeman**

KANSAS



CASING

20	10	
15	8 5/8	519' w/300 sx cem.
12	6	
13	5	

ELEVATION **2354' KB**


PRODUCTION **DRY/MISS.**

FIGURES INDICATE BOTTOM OF FORMATION

0	40
40	115
115	765
765	990
990	1025
1025	1348
1348	1604
1604	1640
1640	2343
2343	2585
2585	2800
2800	2915
2915	3018
3018	3385
3385	3530
3530	3685
3685	3925
3925	4179
4179	4600
4600	4620
	<u>4620</u>

Clay, Limestone
Sand, Shale
Shale, Shells
Redbed, Shale
Anhydrite
Shale, Salt, Sand
Salt, Shale
Anhydrite
Shells & Shale
Shale, Lime
Lime, Shale
Chalky Lime, Shale
Chalky Lime
Chalky Lime, Shale
Chalky Lime
Lime, Shale
Shale, Lime
Lime, Shale
Lime
Lime, Chert
RTD - D. & A.

Log's Count
Anhydrite 1602
* Red " 1640
Kochner 3910
L. Kansas City 3988
Cherokee Sh 4504
Mississippi 4616



8 5/8" used 287 surface casing set @ 519' cemented with 300 sacks of Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Springer A-#1 Well, located 150' South of C SE SE of Section 24, Township 22 south, Range 24 West, Hodgeman County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
Leslie Kite