

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

25-22-24W

COMPANY **LEBEN DRILLING**

SEC. 25 T. 22 R. 24W

FARM **Springer**

NO. **2**

150' E of C NW NE

TOTAL DEPTH **4667'**

COMM. **4-7-67**

COMP. **4-17-67**


SHOT OR TREATED

CONTRACTOR **Leben Drlg.**

ISSUED **5-13-67**

COUNTY **Hodgeman**

KANSAS



CASING

20	10	
15	8	5/8" 490' cem w/ 325 sx
12	6	
13	5	

ELEVATION **2372' KB**

PRODUCTION **DRY/ MISS**

FIGURES INDICATE BOTTOM OF FORMATIONS

0	40	Surface Soil, Clay
40	415	Clay, Shale
415	460	Sand
460	725	Shale
725	1085	Redbed, Shale
1085	1285	Sand
1285	1618	Shale
1618	1646	Anhydrite
1646	2340	Shale, Shells
2340	2640	Shale, Lime
2640	3525	Lime
3525	3740	Chalky Lime
3740	4667	Lime
	4667	RTD - D. & A.

TOPS: SCOUT
 Anhydrite 1618
 Heebner 3920
 Lansing K C 3998
 Cherokee shale 4512
 Mississippi 4609

8 5/8" 20# new and 24# used surface casing set @ 490' cemented with 325 sacks Common cement, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Springer #2 Well, located 150' East of C NW NE of Section 25, Township 22 South, Range 24 West, Hodgeman County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me on this 11th day of May 1967