

26-22-24W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL CO.
Farm- Davis 'D' No. 1

SEC. 26 T. 22 R. 24W
 C NW NE

Total Depth. 4657'
Comm. 3-27-62 Comp. 4-8-62
Shot or Treated.
Contractor.
Issued. 9-29-62

County Hodgeman
 KANSAS



CASING:
3 5/8" 223' cem w/175 sx.
4 1/2" 4654' cem w/150 sx.

Elevation. 2429' KB

Production. 25 BOPD, 26% WTR

Figures Indicate Bottom of Formations.

sand & shale	223
shale & shell	2185
shale & lime	4028
lime	4640
shale, lime & chert	4657 RTD
Total Depth	

TOPS:	
Heebner	3958
Toronto	3974
Lansing	4040
Base Kansas City	4373
Cherokee Shale	4555
Conglomerate Shale	4632
Mississippian Sand	4653

DST #1 4591-4635' op 30 min. Rec. 5' mud.
ICIP 75#/15 min. IF 0#, FF 0#, BHP 0#/
15 min.

DST #2 4630-4657' op 2 hrs. Rec. 70'
oil cut mud, 130' heavily oil cut mud,
60' muddy oil. ICIP 1425#/30 min. IF 75#,
FF 149#, BHP 1387#/30 min.