

KANSAS DRILLERS LOG

API No. 15 — 083 — 20415
County Number

Operator
petroleum, Inc.

Address
800 R.H. Garvey Bldg., 300 W. Douglas

Well No. 1 Lease Name DAVIS 'AH'

Footage Location
1980 feet from (N) (S) line 660 feet from (E) (W) line

Principal Contractor DNB Drilling Co. Geologist H. Filson

Spud Date 1-4-75 Total Depth 4658' P.B.T.D.


Date Completed 1-22-75 Oil Purchaser Cities Service Oil Company

S. 26 T. 22 R. 24 ^{XX}_W

Loc. C. SE NE

County Hodgeman

640 Acres
N



Locate well correctly

Elev.: Gr. 2429'

DF 2422' KB 2425'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{4}$ "	8 5/8"	20#	404'	common	275	2% gel, 3% c.c.
Production	7-7/8"	5 $\frac{1}{2}$ "	15.5#	4648'	50/50 Pozmix	100	18% salt, 2% gel

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at
2-3/8" OD	4641'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 gal Non-E 15%	4648-58' Open hole

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
2-13-75		Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	53 bbls.	MCF	190 bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
None			24 hr.		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Petroleum, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name DAVIS 'AH'	Oil
26 T 22S R 24 XX W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 4647-58 30-30-30-30 Strg. Blow. Rec. 806' GIP, 560' clean gasy oil, 246' mdy gasy oil IFP 33#- 122#, FFP 167#-234#, BHP 1099#-1099#			Dresser-Atlas	
			Anh. 1635	(+790)
			Hbn. 3937	(-1512)
			Tor. 3954	(-1529)
			Lans. 3988	(-1563)
			B/KC 4373	(-1948)
			Cher. 4558	(-2133)
			Cg. 4619	(-2194)
			Miss.Ls. 4634	(-2209)
			Miss. D. 4646	(-2221)
			LTD. 4655'	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



Richard H. Dumbler
Signature
Office Manager
Title
March 14, 1975
Date

State Geological Survey
WICHITA, BRANCH

DRILLERS' LOG

15-083-20415

26-22-24W

PETROLEUM, INC.
No. 1 Davis 'A-B'
C SE NE, Sec. 26-22S-24W
Hodgeman County, Kansas

Elevation: 2425 K.B.

Commenced: 1- 4-75
Completed: 1-13-75

Surface: 396' of 8-5/8"
cemented w/275 sx common
cement, 2% Gel, 3% cc.
1-5-75

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	0 - 404
Shale & Sand	404 - 985
Shale, Sand & Red Bed	985 - 1037
Blaine Anhydrite	1037 - 1050
Shale, Red Bed & Sand	1050 - 1625
Shale	1625 - 1638
Anhydrite	1638 - 1668
Shale	1668 - 2120
Lime & Shale	2120 - 3175
Shale & Lime	3175 - 3405
Lime & Shale	3405 - 4005
Lime	4005 - 4658 T.D.

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state, this 27th day of January, 1975.

My Commission Expires:
August 25, 1976

Ella Priess
Ella Priess, Notary Public

Ella Priess
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Com. Expires Aug. 25, 1976