

State Geological Survey  
WICHITA, BRANCH

26-22-24N

KANSAS DRILLERS LOG

API No. 15 — 083 — 20,416  
County Number

Operator

Dane G. Hansen Trust

Address

Box 187 Logan, Kansas 67646

Well No.

#1

Lease Name

Ford

Footage Location

660 feet from (N) (S) line

660

feet from (E) (W) line

Principal Contractor

C-G Drilling Co.

Geologist

J. E. Jespersen

Spud Date

February 4, 1975

Total Depth

4633

P.B.T.D.

Date Completed

February 13, 1975


Oil Purchaser

S. 26 T. 22 R. 24 E W

Loc. NE SE

County Hodgeman

640 Acres



Locate well correctly

Elev.: Gr. 2381

DF 2383 KB 2386

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	24#	412.56	Common	250	2% Gel, 3% Ca Cl
Production	7 7/8	5 1/2	14#	4624	Salt Sat Cem	100	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
				None	

TUBING RECORD

Size	Setting depth	Packer set at
2"	4600	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 Gal. Regular	Open Hole

INITIAL PRODUCTION

Date of first production 5/2/75		Producing method (flowing, pumping, gas lift, etc.) Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil 7 bbls.	Gas xx MCF	Water None bbls.	Gas-oil ratio xx CFPB	
Disposition of gas (vented, used on lease or sold) vented			Producing interval(s) Open Hole		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Dane G. Hansen Trust		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: OIL
Well No. 1	Lease Name Ford	
S 26 T22 R 24 W		

### WELL LOG


Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand & Shale	0	1080	Anhydrite	1598
Sand	1080	1310	Heebner	3919
Red Bed	1310	1598	Toronto	3933
Anhydrite	1598	1643	LKC	3971
Shale & Sand	1643	2090	BKC	4356
Shale	2090	2300	Marmaton	4381
Lime & Shale	2300	4055	Fort Scott	4521
Lime	4055	4633	Cherokee	4548
RTD	4633		Base Penn	
			Cong.	4599
			Miss Lime	4616
			Miss Dolo	4623
			RTD	4633
DST #1 4598-4633 - Open 30 SI 30 Open 30 SI 30 Rec. 120' GIP - 440' HO&GCM IBHP 534# FBHP 425# IFP 65# FFP 218#				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received



Signature

Manager

Title

May 20, 1975

Date