


State Geological Survey
KANSAS DRILLERS WICHITA, BRANCH

API No. 15 — 083 — 20430
 County Number

Operator Petroleum, Inc.		
Address 800 R.H. Garvey Bldg., 300 W. Douglas, Wichita, Ks. 67206		
Well No. 1	Lease Name FORD 'G'	
Footage Location 1980 feet from XXX (S) line 1980 feet from XXX (W) line		
Principal Contractor DNB Drlg.	Geologist Jay Dirks	
Spud Date 8-1-75	Total Depth 4631 Feet	P.B.T.D.
Date Completed 8-26-75	Oil Purchaser The Permian Corporation	

S. 26 T. 22S R. 24 ^{XXX}_W
 Loc. C. NE SW
 County Hodgeman



Elev.: Gr. 2370
 DF 2372 KB 2375

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8 5/8"	20#	398'	Common	275	2% gel, 3% c.c.
Production		5 1/2"	14 & 15.5#	4630'	50/50 Pozmix	100	10% salt

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
4	DP Jets	4613-16'

TUBING RECORD

Size	Setting depth	Packer set at
2-3/8" OD EUE	4577'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 gal. XW 35 Acid	4613-16'

INITIAL PRODUCTION

Date of first production 9-25-75		Producing method (flowing, pumping, gas lift, etc.) Pumping	
RATE OF PRODUCTION PER 24 HOURS	Oil 100 bbls.	Gas — MCF	Water 60 bbls.
Disposition of gas (vented, used on lease or sold) none		Producing interval (s) 24 hr.	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Petroleum, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name FORD 'G'	Oil
S 26 T 22S R 24 Ex W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 - 4590-4615 Misrun			DRESSER ATLAS LOG	
DST #2 - 4604-4615 30-30-30-60 Weak blow. Rec. 65' HOCM, 60' SOC muddy Wtr. IF 40-53#, BH 1017#-1017#, FF 53#-93#.			Anh. 1595 B/Anh. 1626 Heeb. 3905 Tor. 3930 Lans. 3960 B/KC 4350 Marm. 4376 Ft. Sct. 4512 Ck. Sh. 4536 Cong. 4593 Miss.D. 4612 LTD 4631'	(+780) (+749) (-1530) (-1555) (-1585) (-1975) (-2001) (-2137) (-2161) (-2218) (-2237) (-2256)
DST #3 - 4615-4620 30-30-30-30 Good blow. Rec. 270' oil, 35 grav. 30' SO&GCM, 120' clean water. ISIP 991# in 30, FSIP 991# in 30, IF 13#-119#, FF 119#-185# 120°.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	
	 Signature Office Manager Title Oct. 7, 1975 Date

State Geological Survey
WICHITA, BRANCH

15-C83-20430
26-22-24W

DRILLERS' LOG

PETROLEUM, INC.
No. 1 Ford 'G'
C NE SW, Sec. 26-22S-24W
Hodgeman County, Kansas

Elev: 2372 D.F.

Commenced: 8-1-75
Completed: 8-9-75

Surface Casing: 390' of
8-5/8" cemented w/275sx
common cement, 2% Gel,
3% cc. 8-1-75

FORMATION

DEPTH

Surface Hole	0 - 398
Shale	398 - 975
Blaine Anhydrite	975 - 988
Sand & Shale	988 - 1450
Shale & Red Bed	1450 - 1594
Anhydrite	1594 - 1628
Shale	1628 - 2505
Shale & Lime	2505 - 2670
Lime & Shale	2670 - 3825
Lime	3825 - 4210
Lime & Shale	4210 - 4375
Lime	4375 - 4620
Lime & Conglomerate	4620 - 4625
Lime	4625 - 4630 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
JAMES L. DONELSON



STATE OF KANSAS: ss:

Subscribed and sworn to before me, this 14th day of August, 1975

My Commission Expires:
August 25, 1976

Ella Priess
Ella Priess, Notary Public

