

26-22-24W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **IMPERIAL OIL CO.**
Farm- **Springer** No. **1**

SEC. 26 T. 22 R. 24W
 C NE NW

Total Depth. **4765'**
Comm. **1-25-62** Comp. **2-10-62**
Shut or Treated.
Contractor.
Issued. **6-30-62**

County **Hodgeman**
 KANSAS



Elevation. **2412'** KB

Production. **93 BOPD, 5% Wtr.**

CASING:
8 5/8" 192' cem w/150 sx.
4 1/2" 4764' cem w/150 sx.

Figures Indicate Bottom of Formations.

shale & sand	1245
shale & shell	2430
shale & lime	4055
lime	4630
lime & chert	4645
lime	4665
chert & lime	4690
lime	4765 RTD
Total Depth	

TOPS:	SAMPLE	ELECTRIC
Heebner	3930	3927
Toronto	3947	3944
Brown Lime	4002	4000
Lansing	4012	4010
Base Kansas City	4344	4343
Cherokee Shale	4525	4522
Conglomerate	4006	4604
Mississippian (Warsaw)	4626	4629
Mississippian (Osage)	4742	4742

DST #1 4600-30', op ½ hrs., rec. 5' rotary
mud w/a few specks of oil. ICIP 0#/20 mins.,
IF 0#, BHP 0#/20 mins.

DST #2 4630-45', op 1 hr., rec. 200' gas in
pipe, 250' clean oil, 120' muddy oil, 180'
heavily oil & gas cut mud. ICIP 1370#/20 mins.,
IF 0#, FF 170#, BHP 1220#/20 mins.

DST #3 4647-65', op 1 hr., rec. 40' gas in
pipe, 900' clean oil, 130' very slightly
oil & gas cut water. ICIP 1310#/20 mins.,
IF 0#, FF 310#, BHP 1140#/20 mins.

DST #4 4675-90', op 1 hr, rec. 60' very
slightly oil cut water, 180' water.
ICIP 1310#/20 mins., IF 0#, FF 60#, BHP
1130#/20 mins.