

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


26-22-24W

Company- IMPERIAL OIL COMPANY
 Farm- Springer No.3

SEC. 26 T. 22 R. 24W
 C SW NW

Total Depth. 4640'
 Comm. 11-2-62 Comp. 11 14-62
 Shot or Treated.
 Contractor. Imperial Oil of Kansas, Inc
 Issued. 3-23-63

County Hodgeman
 KANSAS



CASING:

8 5/8" 255' cem w 200 sx.

Elevation. 2377 KB

Production. Dry

Figures Indicate Bottom of Formations.

shale & sand	1720
shale & shell	1980
shale & lime	3750
lime	4598
lime & chert	4620
chert	4630
lime & chert	4640 RTD
Total Depth	

TOPS:	
Heebner	3906
Toronto	3924
Brown Lime	3978
Lansing	3987
Base Kansas City	4323
Cherokee shale	4504
Conglomerate	4589
Warsaw Dolomite	4618

DST #1 4586-4630', op 30 min. weak blow
 Died in 10 min Rec 30' slightly oil
 spotted mud ICIP 1196#, IFP 37#, FFP 57#.
 FCIP783# in 30 min

DST #2 4630-40', op 90 min. Good blow Rec.
 1800' salt water ICIP 1309# IFP 260#, FFP
 708#, FCIP 1309# in 30 min.