

30-22-24W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


Company- FRANCO CENTRAL OIL CO.
 Farm- Campbell No.1

SEC. 30 T. 22 R. 24W
 C NE NW

Total Depth. 4752'
 Comm. 5-11-60 Comp. 5-25-60
 Shot or Treated.
 Contractor. Red Tiger Drilg. Co.
 Issued. 10-8-60

County Hodgeman

KANSAS



Elevation. 2470' DF

Production. Dry

CASING:

8 5/8" 158' cem w/110 sx.
 5 1/2" 4747' cem w/100 sx.

Figures Indicate Bottom of Formations.

surface soil clay	70
shale shells	156
shale & shells	390
sand & shale	550
shale & shells	1020
lime	1085
shale & shells	1510
shale, shells	1580
lime (Anhydrite)	1675
shale, shells	1760
shale & shells	2020
shale & lime	2180
shale & shells	2330
lime & shale	2445
lime, shale	2585
lime	2675
lime & shale	3092
shale & lime	3150
shale, lime	3230
shale & lime	3470
shale, lime	3565
shale & lime	3728
lime	3755
lime, shale	3835
lime & shale	4010
lime	4615
lime & chert	4635
chert	4645
Mississippi	4752
Total Depth	

TOPS: SCOUT

Anhydrite	1580
Heebner	3922
Lansing	3966
Base Kansas City	4308
Marmaton	4392
Cherokee	4510
Conglomerate	4596
Mississippi	4620
Warsaw	4668
Osage	4726