


APR 29 1972

KANSAS CORPORATION COMMISSION

WELL RECORD

(Mail to Kansas Geological Survey, 4150 Monroe Street, Wichita, Kansas 67209)



Lease Name: Rupp Well No. 1
 Well Located: SE NW SE
Hodgeman SEC 9 TWP 22S RGE 25W
 Operator: Francis Oil & Gas, Inc.
 Address: 4120 East 51st Street, Tulsa, Oklahoma 74135
 Elevation: Ground 2519' D.F. K.B.
 Type Well: (Oil, gas, dry hole) Dry Hole

Drilling Commenced: April 3 1972 Drilling Completed: April 5 1972
 Well Completed: April 5 1972 Total Depth 1963'
 Initial Production: _____

Casing Record

Size: 8-5/8" Set at 348.44' Size: _____ Set at _____
 Size: _____ Set at _____ Size: _____ Set at _____

Liner Record

Size: _____ Set from _____ To _____

Cementing

Casing Size 8-5/8" Sacks 200

Type Cement and Additives

Common cement, 2% gel and 3%



Perforations

Formation

Perforated Interval and Number Shots

None

Electric Log Run (Show type log and depths covered)

None

Francis Oil & Gas

Rupp #1

9-22-25W

Show Drill Stem Tests,
Well Stimulation and
Production Tests

Formation	Top	Bottom	
			No drill stem test run.

D R I L L E R S L O G

#1 Rupp

CASING RECORD:
342.44' of used 8-5/8"
face casing.

COMPANY: Francis Oil & Gas, Inc.

DESCRIPTION: SE NW SE
Section 9-22S-25W
Hodgeman County, Kansas

CONTRACTOR: Strata Drilling, Inc.

TOTAL DEPTH:
1963'

COMMENCED: April 3, 1972

ELEVATION: 2519' GL

COMPLETED: April 5, 1972

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay, Sand, Post Rock & Shale	0	367	Ran 342.44' of used 8-5/8" surface casing; set and cemented at 348.44' with 200 sacks of common cement, 2% gel and 3% C. C. Plug down at 10:00 P. M. April 3, 1972.
Shale	367	540	
Shale, Red Bed, Sand Streaks	540	1027	
#1 Anhydrite	1027	1200	
Red Bed & Shells	1200	1224	
Sand	1224	1416	
Red Bed & Shale	1416	1729	
#2 Anhydrite	1729	1963	

Smp Top
SC 729



D. & A.

Plugged hole as follows: Plugged at 660' with 70 sacks of common cement; plugged at 300' with 20 sacks of common cement; plugged at 40' with 10 sacks of common cement. Plug down at 1:00 P. M. April 5, 1972.