

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


9-22-25W
✓

Company- SUNRAY D X OIL
Farm- Louis Schauvliege No. 1

SEC. 9 T. 22 R. 25W
C NE NE

Total Depth. 4788'
Comm. 4-8-64 Comp. 4-17-64
Shot or Treated.
Contractor. Stickle Drlg.
Issued. 7-18-64

County Hodgeman
KANSAS



CASING:

8" 251' cem w/ 285 sx

Elevation. 2524' KB

Production. DRY

Figures Indicate Bottom of Formations.

sand & shale	251
shale & shells	400
shale	1700
shale & shells	2100
shale & lime	2777
lime	2940
shale	3207
shale & lime	3440
shale	3619
shale & lime	4105
lime	4335
lime & shale	4400
lime	4520
lime & shale	4579
lime	4775
cherty lime	4788
Total Depth	

TOPS: SCOUT

Anhydrite	1697
Heebner	3927
Lansing	3975
Base Kansas City	4316
Marmaton	4412
Cherokee shale	4522
Conglomerate (Smp)	4626
Mississippi (smp)	4651
Mississippi Osage	4779