

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-22-25W

Company- KEWANEE OIL COMPANY
Farm- Kline No. 1

SEC. 15 T. 22 R. 25W
SW SE NE

Total Depth. 4746'; PLUGGED BACK 4636'.
Comm. 12-20-57 Comp. 1-7-58
Shot or Treated.
Contractor. Graham-Michaelis Drilling Company
Issued. 3-1-58

County Hodgeman
KANSAS



Elevation. 2502'

CASING:
8 5/8" 563' cem w/300 sx
5 1/2" 4668' cem w/150 sx
2 3/8" 4618.38'

Production. 364.24 barrels oil
Natural, no wtr in 21 hours.

Figures indicate Bottom of Formations.

surface clay & sand	140
B. shale	250
sand-shale	564
shale, gyp & sand	1010
shale	1175
sand	1385
shale	2640
shale & lime	2815
lime	3061
lime-shale	3210
lime-chalk	3355
shale lime	3499
lime	3758
lime shale	3892
lime	4570
lime chert	4580
lime	4595
lime-Coring #2	4745-RTD
lime	4746
Total Depth	

<u>TOPS:</u>	<u>SAMPLE</u>	<u>WELEX RADIATION</u>
		<u>GUARD LOG TOPS</u>
Heebner	3882	3880
Toronto	3897	3897
Douglas	3920	3920
Lansing-Kansas City	3933	3931
Base Kansas City	4327	4327
Marmaton	4356	4350
Basal Pennsylvania Conglomerate	4557	4556
Mississippian	4577	
Mississippi Lime		4571
Mississippi Dolomite		4576

Perforated with 4 bullets per foot from 4584' to 4585' and with 6 bullets per foot from 4577' to 4584'.