

15-22-25W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company. KEWANEE OIL CO.
Farm. Larkin No. 5

SEC. 15 T. 22 R. 25W
NE NW SE
980' fr WL, 330' fr NL, SE/4

Total Depth. 4676 FBTD 4646
Comm. 3-21-57 Comp. 4-19-57
Shot or Treated. Perf. 4 SPF/4611-46, 500 gal. MCA acid.
Contractor. Graham-Michaelis Drilling Co.
Issued. 8-3-57

County Hodgeman
KANSAS



CASING:
9 5/8 @ 555' w/ 400 sx cmt.
5 1/2 @ 4674.12' w/ 100 sx cmt.
2 3/8 @ 4642.52'

Elevation. 2514 CM

Production. 232 BOPD

Figures indicate Bottom of Formations.

sand & clay	65
shale & sand	288
shale	350
sand	400
blue shale	685
shale	715
sand	825
shale & sand	1410
shale & shells	2035
shale & lime streaks	2455
lime & shale	2597
lime	3045
lime & shale	4112
lime	4676
Total Depth	

Plugged back to 4646

TOPS:	SAMPLE	HALLBTN.
Heebner	3894	3891
Toronto	3912	3906
Douglas	3934	3930
Lansing-KC	3945	3942
Base KC	4339	4340
Marmaton	4361	4364
Penn. Basal Conglom.	4564	4568
Mississippi	4603	4602