

15-22-25W


Company- KEWANEE OIL COMPANY  
Farm- Staley No. 4

SEC. 15 T. 22 R. 25W

SE NW NW

983.3' fr NL, 959.61' fr  
WL of the NW/4

County Hodgeman  
KANSAS



Total Depth. 4700'

Comm. 2-22-59

Comp. 3-12-59

Shot or Treated.

Contractor. Graham-Michaelis Drlg. &amp; K &amp; A Drlg.

Issued. 6-20-59

## CASING:

8 5/8" 561.73' cen w/350 sx.

5 1/2" 4687.51' cen w/100 sx.

2 3/8" O.D. Tubing set @ 4658.43'

Elevation. 2493' CM

Production. 34 BOPD

Figures indicate Bottom of Formations.

|              |          |
|--------------|----------|
| surface      | 0        |
| shale & sand | 440      |
| shale        | 575      |
| shale & sand | 840      |
| shale        | 2475     |
| lime & shale | 2709     |
| lime         | 2927     |
| lime & shale | 3145     |
| lime         | 3230     |
| lime & shale | 3877     |
| lime         | 4187     |
| lime & shale | 4280     |
| lime         | 4640     |
| lime & shale | 4664     |
| lime         | 4700 RTD |

Total Depth

Plugged back to 4659'

## TOPS: SAMPLE C.M. MEAS.

|                     |      |
|---------------------|------|
| Heebner             | 3902 |
| Toronto             | 3916 |
| Douglas             | 3940 |
| Lansing-Kansas City | 3950 |
| Base Kansas City    | 4347 |
| Marionton           | 4368 |
| Cherokee            | 4480 |
| Conglomerate        | 4570 |
| Mississippi         | 4603 |

## TOPS: WELEX GUARD LOG C.M. MEAS.

|                     |      |
|---------------------|------|
| Heebner             | 3902 |
| Toronto             | 3915 |
| Douglas             | 3940 |
| Lansing-Kansas City | 3948 |
| Base Kansas City    | 4344 |
| Marionton           | 4366 |
| Cherokee            | 4478 |
| Conglomerate        | 4569 |
| Mississippi         | 4602 |

Treating Record: Acidized w/500 gals. mud  
acid by B J Service.

Perforating Record: Perforated from 4612'  
to 4619' with 28 jet shots. Perforated  
by Welex.