

15-22-25W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- KEWANEE OIL
Farm- Staley No. 5

SEC. 15 T. 22 R. 25W
SE SW NW
2310' FNL & 990' FWL

Total Depth. 4670' PBTD 4640
Comm. 3-14-66 Comp. 4-2-66
Shot or Treated.
Contractor. Gabbert-Jones, Inc.
Issued. 5-28-66

County Hodgeman
KANSAS



CASING:

5/8" O 108.61' w/150 sx.
5 1/2" O 4669.92' w/ 135 sx.

Figures indicate Bottom of Formations.

2479 GR
Elevation. 2192' GB

Production. PMP 20 BOPD & 2 DWD
(MISS 4602-C5)

sand & shale	111
shale	380
shale & sand	1460
shale	1663
Anhydrite	1690
shale & shells	2060
lime & shale	4063
lime	4330
lime & shale	4556
Conglomerate	4586
lime & Dolomite	4670
Total Depth	

TOPS: LOG

Anhydrite	1663
Heebner	3880
Toronto	3897
Lansing-Kansas City	3930
Base Kansas City	4330
Cherokee	4464
Fort Scott	4472
Basal Pennsylvanian	
Conglomerate	4556
Mississippi	4586

Pay Horizon: Mississippi Colomite.

Net Pay: 10'

Additional Pays: None

Perforations: 4602-4605' C.M. w/3 bullets per foot.

Treating Record: 4-1-66-500 gal. 15% MCA-Special w/Anti-sludge Additives.