

NOV 15 1969

27- 22- 25W

WELL LOG

CHIEF DRILLING CO., INC.
Suite 905 Century Plaza
Wichita, Kansas 67202

#1 HEY
SE NW Sec. 27-22-25W
Hodgeman County, Kansas

Contractor: Company tools

Commenced: 10-15-69
Completed: 10-21-69

Casing Record: Set 401' of 8 5/8" w/300
sacks Sunset cement.

Dry

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
			2511 Gr.
Surface Clay	0	40	2513 D.F.
Shale w/sand strks.	40	401	2516 K.B.
Shale w/sand strks.	401	1050	
Shale	1050	1109	
1st Anhydrite	1109	1124	<u>FORMATION TOPS</u>
Shale & shells	1124	1214	1st. Anhy. 1104 +1412
Sand	1214	1394	2nd. Anhy. 1706 + 810
Shale & shells	1394	1706	
2nd Anhydrite	1706	1742	<u>LOG TOPS</u>
Shale & shells	1742	1990	Anhydrite 1705 + 811
Shale, Shells, Lime st.	1990	2454	Heebner 3938 -1422
Lime & Shale	2454	4064	Toronto 3958 -1442
Total Depth	4064		Lansing 3994 -1478
			T.D. 4064 -1548

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the
Driller's Log of the well drilled in the SE NW of Section 27-22-25W,
Hodgeman County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson
Jim Robinson, Office Mgr.

Subscribed and sworn to before me this 24th day of October, 1969.

Betty Brandt
Betty Brandt, Notary Public

MY COMMISSION EXPIRES:
May 9, 1971