

508 East Murdock,

Wichita, Kansas

26-22-26W

Company- KAISER FRANCIS
Farm- Cossman

No. 1

SEC. 26 T. 22 R. 26W
C NE SW

Total Depth, 4850' (53)


Comm. 10-8-63

Comp. 10-22-63

Shot or Treated.

Contractor. K & E Drlg.

Issued. 3-14-64

County Hodgeman
KANSAS

CASING:

Elevation. 2571' KB

8 5/8" 270' cem w/ 175 sx

Production. Dry

Figures Indicate Bottom of Formations.

clay & Post rock	60
sand	85
clay	120
shale & clay	735
sand	860
red bed & shale	1000
shale & shells	1730
shale & red bed	1732
anhydrite	1780
shale & shells	2400
shale & lime	2725
lime	2935
shale & lime	3020
lime	3250
lime & shale	3390
lime	3550
lime & shale	3670
lime	3880
lime & shale	3965
lime	4090
Kansas City lime	4139
lime	4235
lime & shale	4278
lime	4404
lime & shale	4445
lime	4530
lime & shale	4590
lime	4653
chert & lime	4770
lime	4850
Total Depth	

TOPS: SCOUT

Anhydrite (smp)	1780
Heebner	3941
Toronto	3956
Lansing	3987
Base Kansas City	4398
Marmaton	4422
C herokee	4508
Conglomerate	4621
Mississippi	4630
Mississippi St. Louis(smp)	4632
Mississippi Spergen (Smp)	4693
Mississippi Warsaw	4764