

KANSAS GEOLOGICAL SOCIETY 8-22-3W
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY KANTOR OIL

SEC. 8 T. 22 R. 3W
LOC. SW SE NW

FARM Neufeld

NO. 9

TOTAL DEPTH 4371

COMM. 4-19-67

COMP. 5-3-67


SHOT OR TREATED

CONTRACTOR Blackstone Drlg.

ISSUED 6-17-67

COUNTY Harvey

KANSAS



CASING 13" @ 308' w/300 SX

20 10

15 # 7" @ 3773' w/200 SX

12 6

13 5

ELEVATION 1457' KB

PRODUCTION SWDW/ARB

FIGURES INDICATE BOTTOM OF FORMATIONS

0	to	45	Clay
45	to	240	Sand
240	to	395	Shale
395	to	600	Shale & Lime
600	to	690	Lime & Shale
690	to	980	Lime
980	to	1240	Lime & Shale
1240	to	1950	Shale & Lime
1950	to	2285	Lime
2285	to	2505	Sand, Shale & Lime
2505	to	2890	Lime
2890	to	3095	Lime & Shale
3095	to	3160	Shale & Lime
3160	to	3312	Mississippi
3312	to	3363	Lime
3363	to	3465	Shale
3465	to	3612	Lime & Shale
3612	to	3630	Lime
3630	to	3682	Simpson
3682	to	3705	Sand & Shale
3705	to	4309	Arbuckle
4309	to	4344	Lime & Sand
4344	to	4371	Granite Wash
		4371	T. D.

Cut 17 1/4 in. hole to 306 ft. and run 308.90 ft. of 13 in. surface pipe and cemented with 300 sacks on bottom at 306 ft. Plug down at 2:30 P.M., April 10, 1967. Cut 12 1/4 in. hole to 560 ft., then cut 8 3/4 in. hole to 4319 ft. and then cut 7 7/8 in. hole to 4371 ft., and run 3793 ft. of 7 in. casing and cemented with 200 sacks salt saturated Pozmix, 500 foot off bottom at 3781 ft. Plug down at 12:30 A.M., May 3, 1967.

TDPS: Mississippi - 3160' Kinderhook - 3358' Mianer - 3467' Hunton - 3470'
Maquoketa - 3501' Viola - 3610' Simpson - 3630' Arbuckle - 3713'
Granite Wash - - 4344'

Measurements taken from K.B.

CERTIFICATE

I, Charles D. Johnson, Secretary-Treasurer of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct log on your Neufeldt #9, located on the SW 1/4 SE 1/4 NW 1/4 of Sec. 8-22-3W, Harvey County, Kansas as reflected by the files of